

SHREE GANESH ENTERPRISES

All Kinds of Electricals , CCTV , Fire Alarm Systems Works

101/ KAILASH BHAVAN , HANUMAN TEKADI , KOLSHEWADI , KALYAN (E.) 421306

E-mail - sudamtandel72@gmail.com

Mob. 8169749651

Subject: QUOTATION FOR ELECTRICAL SUPPLY & INSTALLATION

Dear Sir / Madam,

As per detail discussion with you, we are glad to attach herewith our reasonable rates for above work, which you will find in order.

SPECIFICATION:

- CONDUITS** : 20 mm & 25 mm PVC Conduits & any ISI make PVC accessories PRECISION make
- WIRES** : Multi core copper conductors 650/1100 Volts. POLYCAB (FR)
- CABELS** : 1.1 KVA armoured copper cabel which would be POLYCAB & any ISI make
- TELEPHONE CABEL** : ITI approved copper wires & cabels. POLYCAB make
- TV CABEL** : 75 ohms co-axial cabel or silver contact cabel. POLYCB make.
- SPEKAR WIRES** : OFC Cabel for ISI make.
- LAN CABEL** : Cat-5 or Cat-6 (ISI make cabel or D' Link)
- EARTHING** : Runing earthing of appropriate gauge of bare copper conductor.
- DISTRIBUTION BOARD** : LEGARAND make.

Rate Copy

SR.NO	DESCRIPTION	RATE	AMOUNT
1	Supply & Installation Of Light Point 3x1.5 sq mm with 20 mm Pvc Pipe & all Assesoris. Upto 20 ft. OlNy.	750	Each
2	Supply & Installation Of Secondary Light Point 3x1.5 sq mm with 20 mm Pvc Conduit & all Assesoris Upto 10 ft. Only.	365	Each
3	Supply & Installation Of 2 Way Light Point 3x1.5 sq mm with 20 mm Pvc Conduit & all Assesoris. Upto 20 ft. Only	1050	Each
4	Supply & Installation Of Light Point 2x2.5 sq mm +1x1.5sq mm earthing wire with 20 mm Pvc Conduit & all Assesoris. Upto 20 ft. OlNy.	1250	Each
5	Supply & Installation Of 5 Amp Plug Point 2x2.5 sq mm +1x1.5sq mm earthing wire with 20 mm Pvc Conduit & all Assesoris. Upto 20 ft. OlNy.	1250	Each
6	Supply & Installation Of 15 Amp Plug Point 2x4 sq mm +1x1.5sq mm earthing wire with 20 mm Pvc Pipe & all Assesoris. Upto 20 ft. OlNy.	1575	Each
	<u>Pvc Conduit</u>		
7	Supply & Installation Of 20 mm MMS Pvc Conduit (Open Type)	23	Rft.
8	Supply & Installation Of 25 mm MMS Pvc Conduit (Open Type)	28	Rft.
	<u>Circuit WiringFrom DB to Switch Board</u>		
9	Supply & Installation Of Circuit wiring From Lighting DB to Switch Board Using 2x2.5 sq mm +1x1.5 sq mm Green Pvc Copper Wire in 25 mm Pvc Conduit.	74	Rft.
10	Supply & Installation Of AC , Gyser & All 15 Amp Power Circuit wiring From Lighting DB to Switch Board Using 2x4 sq mm +1x1.5 sq mm Green Pvc Copper Wire in 25 mm Pvc Conduit.	94	Rft.
11	Supply & Installation Of Bell Circuit wiring From Main Dore to Kitchen & Servent Room Using 3x1 sq mm Pvc Copper Wire in 20 mm Pvc Conduit.	50	Rft.
12	Supply & Installation Of Long Point Circuit wiring 3x1.5 sq mm Wire Runing in 20 mm Pvc Conduit.	60	Rft.
13	Supply & Installation Of 3 Phase wiring From Lighting DB to Switch Board Using 4x4 sq mm +1x2.5 sq mm Green Pvc Copper Wire in 25 mm Pvc Conduit.	152	Rft.
14	Supply & Installation Of 3 Phase wiring From Lighting DB to Switch Board Using 4x6 sq mm +1x2.5 sq mm Green Pvc Copper Wire in 25 mm Pvc Conduit.	216	Rft.
15	Supply & Installation Of 3 Phase wiring From Lighting DB to Switch Board Using 4x10 sq mm +1x4 sq mm Green Pvc Copper Wire in 32 mm Pvc Conduit.	342	Rft.

SR.NO	DESCRIPTION	RATE	AMOUNT
16	Supply & Installation Of Automation wiring From Lighting DB or Switch Board to Light Point Using 2x1.5 sq mm Pvc Copper Wire in 25 mm Pvc Conduit & All Assesoris.	49	Rft.
17	Supply & Installation Of Automation wiring From Lighting DB or Switch Board to Light Point Using 3x1.5 sq mm Pvc Copper Wire in 25 mm Pvc Conduit & All Assesoris.	60	Rft.
18	Supply & Installation Of Automation wiring From Lighting DB or Switch Board to Light Point Using 4x1.5 sq mm Pvc Copper Wire in 25 mm Pvc Conduit& All Assesoris.	71	Rft.
19	Supply & Installation Of Automation wiring From Lighting DB or Switch Board to Light Point Using 5x1.5 sq mm Pvc Copper Wire in 25 mm Pvc Conduittall & All Assesoris.	82	Rft.
20	Supply & Installation Of Automation wiring From Lighting DB or Switch Board to Light Point Using 6x1.5 sq mm Pvc Copper Wire in 25 mm Pvc Conduittall & All Assesoris.	94	Rft.
<u>Data.Voice.Camera & TV Cabeling</u>			
21	Supply & Installation Of Deta & Voice wiring Using Cat 6 Cabel ('D' Link) in 20 mm Pvc Conduit.	34	Rft.
22	Supply & Installation Of Deta & Voice wiring Using Cat 5 Cabel ('D' Link) in 20 mm Pvc Conduit.	30	Rft.
23	Supply & Installation Of TV Cabel wiring Using RG 6 Cabel (Polycab) in 20 mm Pvc Conduit.	34	Rft.
24	Supply & Installation Of TV Cabel wiring Using RG 11 Cabel (Polycab) in 20 mm Pvc Conduit.	65	Rft.
25	Supply & Installation Of Camera Cabel wiring Using RT 4 Cabel (ISI) in 20 mm Pvc Conduit.	34	Rft.
26	Supply & Installation Of Using RG 59 Cabel (Polycab) in 20 mm Pvc Conduit.	28	Rft.
<u>Music System</u>			
27	Supply & Installation Of Spekar Point wiring Using 2core 40/36 Silver/ Coper type Trasparent wire in Pvc Conduit Upto 25 ft. Olny.	1250	Each
28	Supply & Installation Of Spekar Circuit wiring Using 2core 40/36 Silver/ Coper type Trasparent wire in Pvc Conduit After 25 ft.	75	Rft.
29	Installation Of Spekar Point wiring Only Lebour With Supply Of 20 mm MMS Pvc Conduit & All Assesoris 25 ft. Olny.	550	Each
30	Installation Of Spekar Circuit wiring Only Lebour With Supply Of 20 mm MMS Pvc Conduit & All Assesoris After 25 ft.	34	Rft.
<u>G I Juction Box & S S Plate</u>			
31	Supply & Installation Of 100x100 mm 16 Gage G I Floor & Cilling Juction Box	250	Each
32	Supply & Installation Of 150x150 mm 16 Gage G I Floor & Cilling Juction Box	350	Each
33	Supply & Installation Of 200x200 mm 16 Gage G I Floor & Cilling Juction Box	400	Each
34	Supply & Installation Of 250x250 mm 16 Gage G I Floor & Cilling Juction Box	550	Each
35	Supply & Installation Of 300x300 mm 16 Gage G I Floor & Cilling Juction Box	700	Each
36	Supply & Installation Of 350x350 mm 16 Gage G I Floor & Cilling Juction Box	750	Each
37	Supply & Installation Of 400x400 mm 16 Gage G I Floor & Cilling Juction Box	950	Each
38	Supply & Installation Of 450x450 mm 16 Gage G I Floor & Cilling Juction Box	1250	Each
<u>Temporary Lighting</u>			
39	Supply & Installation Of 50 Watt LED Bulb & Pendent Holder	950	Each
40	Supply & Installation Of Temporary Lighting Wiring (Per Point)	450	Each

SR.NO	DESCRIPTION	RATE	AMOUNT
41	Supply & Installation Of 2 Switch 2 Socket Gang Box with Wiring (Comple Set)	375	Each
42	Supply & Installation Of 1x36 Watt Tube Light Fitting	300	Each
43	Supply & Installation Of 5x15 Amp Switches Socket Combine	150	Each
	<u>Light Fittings Installation</u>		
44	Installation Of 1x13,18 Watt CFL Fitting	150	Each
45	Installation Of 2x13,18,24,26 Watt CFL Fitting	175	Each
46	Installation Of 1x36 Watt Mirror Optic Fitting	175	Each
47	Installation Of 2x36 Watt Mirror Optic Fitting	175	Each
48	Installation Of 1 Watt LED Inground Fitting	150	Each
49	Installation Of 3 Watt LED Inground Fitting	175	Each
50	Installation Of 3,5,8,9,10,12,15 Watt LED Fitting	175	Each
51	Installation Of 18,21,24,26,28, Watt LED Fitting	175	Each
52	Installation Of LED Strep Fixing	75	Mtr.
53	Installation Of Wall Light Fitting Fixing	125	Each
54	Installation Of Fan Hook Fixing	750	Each
55	Installation Of Fan Fixing	180	Each
56	Installation Of Exhaust Fan Fixing	150	Each
57	Installation Of 12x50 Halogen Fitting Fixing	150	Each
58	Installation Of Chandelier Fixing Rate Will be Chindiler Size.		
59	Installation Of Hanging Light	150	Each
60	Installation Of Bolard & Gate Light	180	Each
61	Installation Of Dome Light	150	Each
62	Installation Of T-5 Fitting Fixing	125	Each
63	Installation Of Spike Light Fixing	125	Each
	<u>Installation Of Anchor Roma Switches</u>		
64	Installation Of 2 Module Council MS Box	75	Each
65	Installation Of 3 Module Council MS Box	100	Each
66	Installation Of 4 Module Council MS Box	150	Each
67	Installation Of 6 Module Council MS Box	200	Each
68	Installation Of 8 Module Council MS Box	250	Each
69	Installation Of 12 Module Council MS Box	300	Each
70	Installation Of 16 Module Council MS Box	350	Each
71	Installation Of 2 Module to 6 Module Surface Box	75	Each
72	Installation Of 8 Module to 16 Module Surface Box	120	Each
73	Installation Of 1 Module Plate	60	Each

SR.NO	DESCRIPTION	RATE	AMOUNT
74	Installation Of 2 Module Plate	75	Each
75	Installation Of 3 Module Plate	100	Each
7	Installation Of 4 Module Plate	150	Each
77	Installation Of 6 Module Plate	175	Each
78	Installation Of 8 Module Plate	200	Each
79	Installation Of 12 Module Plate	250	Each
80	Installation Of 16 Module Plate	300	Each
81	Installation Of Doore Switch	250	Each
	<u>Electrical Panel</u>		
82	Supply & Installation Of Powder Coated Fabrication 3' x 4' (As Per Design) Aprox.	95000	
<p>Note :- Value Added Tax (GST) 18 % will be charged as applicabel. Any additional work will be subejct to extra chagces. For higher capacity service and meter arrangement charges will be extra This rate charged is as per the Market Rate Outstation Charges of 20% on Bill Amount Rate Validaty : Six Month from the date of submission of the Quotation</p>			